

**ADDENDUM No. 03**

**The Corporation of the Town of Moosonee  
Bay Road & Second Street Sanitary Sewer,  
Watermain and Road Reconstruction  
EXP Project No.: NWL-21018732  
EXP Project No.: NWL-21023124**

**Issued: April 27, 2022**

**Prepared By:** EXP Services Inc.

**Requirements:**

This addendum forms part of the Contract Documents and amends the original Specifications and Drawings, as noted below.

**AMENDMENTS TO ITEM SPECIAL PROVISIONS**

The Item Special Provisions Part B page 9 has been deleted in their entirety and replaced by Part B page 9, Addendum No. 3.

**Attachments:**

Item Special Provisions Part B Addendum No. 3, Page 9

Maintenance holes shall be monolithic with frost straps, and of the size specified in the contract drawings. Frost straps shall be installed as detailed in OPSD 701.100, November 2018, Rev 3.

**407.07.14                      Benching and Channeling**

Subsection 407.07.14 of OPSS 407 is amended as follows:

The inside, concrete bottom of all storm structures shall be benched to appropriately direct flows.

**407.05.04                      Steps and Ladders**

Subsection 407.05.04 of OPSS 407 is amended as follows:

Ladders shall be as detailed in OPSD 405.020, November 2018, Rev 4.

**ITEM 10                      300mm DIA. PIPE STORM SEWER**

**OPSS.MUNI 410, November 2018 – Pipe Sewer Installation in Open Cut, is amended by the following:**

**410.05                              MATERIALS**

Subsection 410.05.01 of OPSS.MUNI 410, is amended by the following:

Pipe insulation to be HI-60 Styrofoam or pre-approved equal. Pipe materials shall be smooth inside wall plastic pipe with bell and spigot joints and elastomeric gaskets. Minimum pipe stiffness shall be 320Kpa.

**410.05.01.05                      Polyethylene Pipe Products**

Subsection 410.05.01.05 is amended by the addition of the following.

Boss 2000 HDPE, and Boss 3000 HDPE will be considered an acceptable alternative for the storm sewer for the purposes of this contract.

**410.05.01.06                      Polypropylene Plastic Pipe Products**

Subsection 410.05.01.06 is amended by the addition of the following:

Sanitite HP will be considered an acceptable alternative for the storm sewer for the purposes of this contract.

**410.07                              CONSTRUCTION**

Section 410.07 of OPSS.MUNI 410, is amended by the following:

Insulation to be installed as per contract documents, 300 mm above the top of the pipe and to be 2.5 m wide. Refer to contract documents for thickness requirements.